



PROJECT
ARIZONA DEPT. PUBLIC SAFETY
JOB NO.
0712-01
SITE NAME
KEYSTONE PEAK &
CASA GRANDE MOUNTAIN, AZ

NOTES:

29 OF 33

A-139284

1. ALL PLYWOOD SHALL BE NAILED EVERY 12" O.C. AND 6" AROUND PERIMETER.
2. HOUSE WRAP TO BE INSTALLED 1/8" BELOW SHEETING AND EXTEND TO TOP OF TOP PLATE. ALL SEAMS TO BE LAPPED 6" AND TAPED W/SEAM TAPE.
3. ALL SCREW HOLES THROUGH PANELS FILLED WITH POLYURETHANE CAULK PRIOR TO SCREW BEING INSTALLED.

BUILDINGS, INC.			
Thermo Bond			
P.O. Box 445 Elk Point, SD			
Scale:	NONE	Title:	BUILDING CONSTRUCTION DETAILS
Date:	1/31/08	Revised:	2/4/08
Drawn By:	TLH	Drawing Number:	AGB8015
Approved By:		COMPUTER AIDED DRAWING AGB8015D	PAGE 7 OF 9